

पी.एम. श्री केन्द्रीय विद्यालय आर्मी एरिया
डी ए डी कॉम्प्लेक्स के पास, वनोवारी रेंज, तुल्लानगर, पुणे 411040
P M SHRI Kendriya Vidyalaya Army Area,
Near DAD Complex, Wanowrie Range, Lulla Nagar Pune 411040
CBSE Affiliation No. 34050 KVS School Code 1226

दूरभाष/Phone No. 020-29705314

वेबसाइट/Website: <https://armyareapune.kvs.ac.in/>

ईमेल/Email: kvarmyareapune1@gmail.com

दिनांक : 11/03/2024

पी. एम.श्री केन्द्रीय विद्यालय आर्मी एरिया पुणे में कर्मचारी आवासीय परिसर के मरम्मत कार्य हेतु सीलबंद निविदा आमंत्रित की जाती है।

निविदा सीलबंद लिफाफे में दिनांक 17/03/2024 को शाम 5:00 बजे तक केन्द्रीय विद्यालय आर्मी एरिया में रखे बॉक्स में डाली जा सकती है तथा दिनांक 18 मार्च 2024 को सुबह 10:00 बजे समिति के सदस्यों के समक्ष खोली जाएगी। समय पश्चात दी गयी निविदा पर कोई विचार नहीं किया जाएगा।

अन्य जानकारी हेतु किसी भी कार्यदिवस विद्यालय में कार्यालय में संपर्क कर प्राप्त की जा सकती है।

कर्मचारी आवासीय परिसर में होने वाले मरम्मत कार्यों का विवरण निम्नलिखित है :

S. NO	NAME OF WORK	NATURE OF WORK	MATERIAL USED
1	Repair work	Bathroom repairing(replacement of broken floor tiles)	1X1 feet tiles (20 nos)
2	Electricals repairing work	Replacement of switches ,plug pin, capacitor,plug point,MCB	Switches -32 Plug pin -6 Capacitors - 12 Plug points -6 MCB - 4
3	Sliding windows	4'x4'- 64-sq. feet's (05 nos) 5'x4'- 320 sq. feet's (17 nos)	Aluminium frame, glass, iron mesh. Aluminium frame, glass, iron mesh.
4	Doors	(06 nos) 6'x3'- 320	PVC without frame
5	Sewage line repairing & clearance of Chambers	01(length of sewage line 70-80m)	
6	Repairing of Rain water drain(Cementing work)	01(length 60-70m)	
7	Plumbing Work		
	(i) Bib cock -12nos	12(replacement)	
	(ii) pillar cock -4 nos	4 (replacement)	

SCOPE OF WORK

Civil Work:

- All toilet and washroom white cement work with waterproofing liquid.
- Repairing of wall cracks inside, stair corridors and entrance chazzas.
- Drainage and sewage line repair concrete all area around sunk tank (backside of B and C type of quarters).
- Replacement of old windows with new aluminium framed sliding windows with good quality glass and wire mesh.
- Repairing of toilets of 2 quarter.
- Fluorescence is caused due to entry of moisture into the brick work and soaking in it to saturation.
- Porous nature of structure cracks in the wall, small trees and plants in the wall.
- Waterproofing in Construction

Plumbing Work:

- All leakage pipes repairing backside of quarter.
- In type-III quarter repair and replace of all leakage pipes and broken pipe (drainage, sewage)
- 12 tap change
- 4 pillar cock (wash basin cock)

Electrical Work:

- 5A = 32 no change
- Capacitor = 12 change,
- Plug pin = 6
- Plug point = 6
- MCB 32Amp = 4




ADDITIONAL TERMS AND CONDITIONS


1) Bidder has to visit the Vidyalaya for UNDERSTANDING THE NATURE AND PLACE OF WORK for real execution.

2) Contractor has to replace the damaged goods.

3) Contractor has to provide GST Bills.

Committee members:

- 1) Mr. Arun chaudhary 
- 2) Mr. D.N khatoi 
- 3) Mr. Yudhvir 


11.3.24
PRINCIPAL

प्राचार्य/PRINCIPAL
केंद्रीय विद्यालय/KENDRIYA VIDYALAYA
आर्मी एरिया/Army Area
पुना-40/Pune-40